

BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE


Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT50560

NAME OF WORK: Improvements to Drains in Bagalagunte in ward No.14, Dasarahalli Sub Division

Sl. No	Description of work	Unit	Qty	Rate quoted by the contractor Sri MANJUNATH N	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Removing and refixing stone slabs of drains and pointing in CM (1:3)	Sqm	488.25	85.99	Rupees Eighty Five and Ninety Nine Paise Only
2	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications	Cum	279.00	176.81	Rupees One Hundred Seventy Six and Eighty One Paise Only
3	KSRB 15.2.1 Providing flush pointing to stone slab pavements, with cement mortar 1:3, after raking joints, nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	697.50	36.03	Rupees Thirty Six and Three Paise Only
4	Providing precast slab of 100 mm thick including cost of all materials, labour, curing, transportation, loading, unloading, etc., complete as per the direction of engineer in charge	Sqm	209.25	1805.57	Rupees One Thousand Eight Hundred Five and Fifty Seven Paise Only



Signature of the Contractor



Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,